



PROJECT REPORT

ALUMANATE ACM

Location: Virginia Beach, VA

Value: \$29,998,000

Completion Date: In Progress

Fabrication: Procon Enterprise

Wall Cladding: Alumanate aka Alusignpanel

Architect: Waller Todd & Saddler

General Contractor: S.B. Ballard



PROJECT DETAILS

The Housing Resource Center will provide efficiency apartments, family and single shelters, supportive services, a health clinic and other community resources in one facility, making it the first of its kind in the region. The \$30 million center will be built at 104 N. Witchduck Road near Southern Boulevard.



Alumanate ACM
SQ FT: 63,500 SQ. FT.
Core Material: Fire Resistent FR
Panel Thickness: 6mm
Panel Dimensions: 62" x 196"
Aluminum Skin Thickness: 0.020"
Color: Color selected by Wall Todd & Saddler
Coating: 3-Coat Fluoropolymer

CONTACT

Alumanate ACM
541-357-8744
www.alumanate.com
sales@alusignpanel.us